

Meadow Brook Storage Building

Date: October 10th, 2025

1. Notification of minor site plan changes

Meadow Brook Golf Course is being required by the states plumbing code to install a ½ bathroom in our planned storage building

The ½ bathroom will be located in the inside back right corner of the storage building

In order to do that we will need to bring a ¾ inch water line to the building and the bathroom

The proposed location of the water line is marked in blue on the site plan

The water line will be brought in from our current Maintenance building. The water line will be required to be 4 feet deep. The path will be under our existing and new gravel lot. The path will not be located inside of the tree line.

A sewer line will also be needed and that is marked in green on the site plan

The bathroom sewer line will be directed to a E One ejector jump located in a chamber to the right of the building. This is also marked in green on the site plan

This sewer line will also be 4 feet deep and run under the existing and new gravel lot.

The sewer line will tie into an existing sewer line located outside of the existing maintenance building

The excavation company will install additional silt fence where we are digging outside of the existing silt fence.

Both the water line and sewer line will be installed in a 24" wide and 4 ft deep trench

Because of the E One pump, the location of the oil and gas separator will be relocated to the right side of the building

Please reach out with any additional questions.

Sincerely,

Daniel McCarthy

McCarthy Enterprises Inc. and Meadow Brook Golf Club